

Roadway Improvement Project

Hunkins Pond Road - Phase II Sanbornton Y Project Sanbornton, NH



The Town of Sanbornton, funded by grant match assistance through the NHDOT Municipally Managed State Highway Aid program, continued with their rehabilitation program for an 8300 LF portion of Hunkins Pond Road. Phase I previously addressed emergency repairs to a small 1500 LF segment of the roadway. Phase II provided for a complete rehabilitation program for approximately 3640 LF of this major east-west corridor for the Town.

QCC, as a sub-consultant to The H.L. Turner Group Inc., undertook an Engineering Study for the complete roadway and developed three rehabilitation program alternatives. Based on the Engineering Study, QCC developed construction documents and provided construction administration for a roadway rehabilitation program that included new roadside drainage swales, underdrains, replacement cross culverts, in-place reclamation of pavements, roadbed reinforcement, importation of crushed gravels for added structural strength, new bituminous pavements and crushed gravel shoulders. Due to a limited Prescriptive Highway Easement for the roadway corridor, the rehabilitation program maintained the existing horizontal geometrics but provided slight modification of vertical geometrics for superelevation and sight distance.

The design of the project was completed in 2008, and the project was bid and constructed in 2009.

Contact:
Robert Veloski
Town Administrator
P.O. Box 124
Sanbornton, NH 03269
(603) 286-8303



QUANTUM CONSTRUCTION CONSULTANTS, LLC