

Roadway Improvement Project

Hunkins Pond Road - Phase III Sanbornton Y Project Sanbornton, NH



The Town of Sanbornton, funded by grant match assistance through the NHDOT Municipally Managed State Highway Aid program, will conclude the rehabilitation of Hunkins Pond Road. Phase III provides rehabilitation for a 3100 LF portion of the roadway and will finish the repairs to the Phase I section.

QCC, as a sub-consultant to The H.L. Turner Group Inc., prepared construction documents based on the Engineering Study that was undertaken for the complete roadway project. The roadway rehabilitation program for this section of the project included new roadside drainage swales, underdrains, replacement of cross culverts, in-place reclamation of pavements, roadbed reinforcement, importation of crushed gravels for added structural strength, new bituminous pavements and crushed gravel shoulders. The section of roadway that underwent emergency repairs in Phase I was completed by installing pavement reinforcement a bituminous pavement wearing course. The existing horizontal geometrics were maintained and slight modifications were made to the vertical geometrics for superelevation.

Contact:
Robert Veloski
Town Administrator
P.O. Box 124
Sanbornton, NH 03269
(603) 286-8303

The design of the project was completed and the project was bid in 2010. Construct began in the fall of 2010 and was completed in the spring of 2011.



QUANTUM CONSTRUCTION CONSULTANTS, LLC